



RFP#-003

Harris Sand & Gravel's RFP-003 covers the materials and labor to install 2 each 2" HDPE conduits along the north side of Pioneer Dr. from the corner of Hazelet Ave. to the corner of Meals Ave. This would include the installation of 2 each new 4'x4' vaults to be located at the corner of Hazelet Ave. and Pioneer Dr., and on the north side of Tatilek Ave. and Pioneer Dr. It also includes the relocation of an existing vault on the corner of Hazlet Ave. and Pioneer Dr. which would be relocated on the corner of Meals Ave. and Pioneer Dr. The installation would follow the same specifications used on Egan Dr. and West Hanagita fiber system. 3M electronic locator balls will be placed in the vaults and a #12 tracer wire will be installed in all the conduits.

Stephen L Hocking Jr
Superintendent
Office: 907-835-4756
Cell: 907-255-2697
steveatharris@hotmail.com

Frontier Electrical Services

PO Box 3030
Valdez, AK 99686
907-835-4810

PROJECT BID

| Date | Bid # |
|-----------|-------|
| 4/24/2025 | 508 |

Name / Address

Harris Sand and Gravel
P.O. Box 6
Valdez, AK 96686

Lines 1 & 2 not
included in CO#1

| Description | Qty | Cost | Total |
|--|--------------|----------------------|----------------------|
| Pioneer Street HDPE install. Bid includes installing 4 vaults and running 2 each 2" HDPE conduits from City Hall to corner of Hazelet. Bid includes installing HDPE to vault at city hall but not installing the 2" rigid conduit to the second floor. HDPE will be left in a vault towards the front of the court yard so it can be ran into the building in the future. Bid does not include excavation work, bedding sand, back fill, or setting the vaults. | 1 | 67,500.00 | 67,500.00 |
| Install HDPE from vault at Tatitlek Ave to Meal Ave. The vault that is currently installed at the corner of Hazelet will be moved to Meals and reused. Bid includes running 2 each 2" HDPE conduits | 1 | 16,500.00 | 16,500.00 |
| Install HDPE down Pioneer drive from Hazelet ave to Meals ave. Install 2 new concrete 4'x4' vaults at the corner of Hazelet ave and Pioneer drive and a vault at Tatitlek ave and Pioneer drive. The vault that is currently installed at the corner of Hazelet will be moved to Meals and reused | 1 | 56,500.00 | 56,500.00 |
| | | Total | \$140,500.00 |

Price guaranteed for 30 days

Signature _____