

Stageline SL100 Mobile Stage

Floor Size: 24' x 20'
 Wind Resistance: 115 mph without windwalls
 Trailer Weight: 9,990 lb



Standard Equipment *	\$	122,500
Options & accessories	\$	33,935
Transport & Training	\$	21,390
Sub-Total	\$	177,825
Discount	-\$	7,825
Total	\$	170,000

All prices are in USD

Taxes not included (if applicable)

Payment terms: 30% to confirm, balance prior to departure

Approval

Date:

Signature:

Name:

EIN # (if applicable):

STANDARD EQUIPMENT ***ROOF STRUCTURE & RIGGING**

4 Built-in trusses / aluminum 2" diameter tube trussing
 24 Built-in rigging points - 4 movable rigging brackets included
 Rigging bar / 14' - spans 2 rigging points from left to right
 2 side overhang rigging beams 6'
 Rigging points in front of corner posts
 4 Aluminum corner posts
 Fiberglass roof molded and wrapped around structure - black roof
 Rigging load capacity tested at twice the working load
 Total roof load capacity with sound wings:
 Galvanized steel column - one on each side

Compatible with industry clamps
 Capacity: up to 1,500lb
 Capacity: 30 lb / ft
 Capacity: 1500 lb per side
 Capacity: 1500 lb per side
 Added roof stability and safety

11,800 lb
 System safely hoists rigged loads

HYDRAULICS

Double mast lifting mechanism (for a fully hydraulic set up of the stage, roof, sound, lighting and other equipment)
 High power integrated hydraulic system
 4 Hydraulic stabilizers / stage levels from 3' 6" to 4' 3"
 Vertical support capacity (each): 15,000 lb
 Lateral support capacity (each): 2,000 lb
 Gas engine

Lifting Capacity: 3,800 lb - balanced load

Equipped with safety valves on all cylinders
 No tools required

No other power source required

STAGE

Plywood, black finish, non slip / quick levelling legs
 Multifunctional extruded aluminum deck edges
 Guardrails (stage model) / aluminum
 Support brackets built-in for Stageline platforms
 Aluminum stairway - 7 steps - adjustable - 35" wide - with handrails
 4 LED work lights

24' x 20'
 To install decks, skirts, guardrails & staircases
 5 x 5' 9" + 2 x 2' 8"
 Full perimeter

2 in the roof, 2 on the chassis

TRAILER

Drawbar with pintle eye
 2 Leaf spring axles
 4 Tires
 Electric brakes on all wheels
 Emergency breakaway system
 Storage compartment
 Spare wheel / full-size rim / integrated storage
 2 Storage bumpers
 10 Equipment tie-downs
 Storage weight capacity
 Storage space capacity

Capacity: 14,990 lb
 0.40 m (16")

DOT requirement
 14" x 16" x 36"

Protects structure

2,268 Kg (5,000 lb)
 23' 10" x 5' 6" x 5' 6" = 720 ft³

STANDARDS & CERTIFICATIONS

Applicable regulations
 Vertical load:
 Wind resistance:

IBC, SAE, DOT, NFPA, CBC, NBC & CWB
 Floor: 7.18 KPa (150 psf) / Roof: 1 KPa (20 psf)
 115 mph without windwalls
 77 mph with windwalls

Certificate stamped by professional engineers
 All technical documents supplied
 24/7 service support +1(800) 267-8243

OPTIONS & ACCESSORIES

A	WINDWALLS - SKIRTS	VINYL/ SCRIM	Price (USD)	Quantity	
a1	Upstage fire retardant windwall - 44' long x full height (with doors) (keder aluminum track system for easy installation) - black	VINYL	\$ 4,200	1	\$ 4,200
a2	Backdrop - 24' x 15' - black		\$ 1,650		
a3	Downstage windwall extensions - 10' 3" x 15' (with doors) - (Set of 2) - black		\$ 2,300		
a4	Skirting - 40' x 4' - black	VINYL	\$ 1,350	1	\$ 1,350
a5	Skirt extension - 8' 6" - black		\$ 295		
* for options a1 to a5, select material - also available in grey - fabrication delay					
B	SOUND WINGS & RIGGING		Price (USD)	Quantity	
b1	Extension platforms (black non-slip) & accessories - 4' x 8' - (sugg'd qty: 4)		\$ 990	4	\$ 3,960
b2	Guardrails (platform model) / aluminum - 3' 8" - (sugg'd qty: 8)		\$ 180	8	\$ 1,440
b3	Reinforced flybays with line array and screen rigging points (set of 2)		\$ 1,750	1	\$ 1,750
b4	FOH pipes - capacity: 700 lb - (set of 2)		\$ 1,830		
b5	Movable rigging brackets - (set of 2)		\$ 150	1	\$ 150
b6	2 Cylinder locks (corner post substitute)		\$ 500	1	\$ 500
C	BANNER SUPPORTS		Price (USD)	Quantity	
c1	Rooftop banner support posts - 37' x 4'		\$ 725	1	\$ 725
c2	Banner framing bars		\$ 450	1	\$ 450
c3	Lateral banner supports - 6' x 15' 10" - includes pulley rigging points for retractable banner system		\$ 800	1	\$ 800
c4	Lateral bars at stage level / keeps lateral banners taut		\$ 900	1	\$ 900
D	UPSTAGE DECK UPGRADE - Extend to 24' x 24'		Price (USD)	Quantity	
d1	3 Extension platforms & accessories - 4' x 24'		\$ 2,970		
d2	8 Guardrails (platform model) / aluminum - 3' 8"		\$ 1,440		
d3	Bracing system for extension platforms		\$ 810		
d4	Windwall to cover increased area		\$ 540		
E	HYDRAULICS		Price (USD)	Quantity	
e1	Hydraulic quick connectors		\$ 450	1	\$ 450
e2	Electric motor, 1 hp, 110 V, hydraulic connections and pump for dual power (steel storage compartment included)		\$ 2,500	1	\$ 2,500
e3	Safety cut off switch		\$ 675	1	\$ 675
F	REVERSIBILITY		Price (USD)	Quantity	
f1	Keder to receive windwalls on downstage roof panels		\$ 350	1	\$ 350
f2	Hardware to receive flybays, lateral banners and FOH pipes on upstage roof panels		\$ 2,160	1	\$ 2,160
H	TRAILER HITCH		Price (USD)	Quantity	
h1	Gooseneck / kingpin for 5th wheel hookup (instead of drawbar with pintle eye)		\$ 2,100	1	\$ 2,100
h2	Gooseneck / ball hitch hookup (instead of drawbar with pintle eye)		\$ 2,100		
h3	Ball hitch (attachment only)		\$ 1,100		
h4	Drawbar / pintle hitch (in addition to gooseneck)		\$ 2,400		
h5	Hydraulic foldable gooseneck for kingpin or ball hitch (instead of drawbar with pintle eye)		\$ 5,500		
I	ACCESSORIES		Price (USD)	Quantity	
i1	Aluminum stairway - 7 steps - adjustable - 35" wide - with handrails		\$ 1,500	1	\$ 1,500
i2	Loading ramp / aluminum - 3' x 12'		\$ 1,325		
i3	Loading ramp / aluminum - 4' x 12'		\$ 2,300		
i4	ADA lift - up to 5' - 600 lb max load - portable - access from all sides		\$ 9,790		
i5	Extension platform (black non-slip) & accessories - 4' x 8'		\$ 990		
i6	Extension platform (black non-slip) & accessories - 4' x 4'		\$ 800		
i7	Guardrail (platform model) / aluminum - 3' 8"		\$ 180		
i8	Guardrail (stage model) / aluminum - 2' 8"		\$ 160		
i9	Guardrail (stage model) / aluminum - 5' 9"		\$ 320		
i10	Guardrail (stage model) / aluminum - 5 x 5' 9" + 2 x 2' 8"		\$ 1,900		
i11	Quick shelter, polyester roof and walls - 8' x 8'		\$ 1,600		
i12	Quick shelter, polyester roof and walls - 10' x 10'		\$ 1,800		
i13	Storage compartment / steel - 14" x 16" x 36"		\$ 775		
i14	Underfloor storage system for options and accessories		\$ 2,500	1	\$ 2,500

21-Dec-18

City of Valdez, AK

Rev 3

OPTIONS & ACCESSORIES

J	LIGHTING & SOUND	Price (USD)	Quantity	
j1	Basic lighting package 8 x LED Par64 Par cans - DMX controllable - 1 x DMX lighting controller, all clamps, plugs and cables	\$ 4,500	1	\$ 4,500
j2	Basic sound system 2 x active 550 watt 2 way PA speaker system with stands & cables / 1 x 6 channel analog mixer with cables, 2 x unidirectional microphones with stands & cables	\$ 3,500		
j3	Power distribution - portable - 50 amp for basic sound and lighting package	\$ 2,350		
j4	Generator - portable 4,500 watt - powers sound and lighting (65 dB 24')	\$ 4,995		
	Road Cases - options:			
j5	Basic lighting package	\$ 975	1	\$ 975
j6	Basic sound system package	\$ 1,600		
j7	Basic lighting and sound system package	\$ 2,450		
K	TRAILER GRAPHICS	Price (USD)	Quantity	
k1	Logo only	TBD		
k2	Full graphic trailer wrap - (2 x (24' 7" x 7' 2") - 2 x (4' 11" x 7'))	\$ 3,675		
	Customized scrim* banners - printed graphics - 4 color process			
k3	Rooftop header banner - 24' x 3' 10"	\$ 970		
k4	Rooftop header banner - 37' x 3' 10" - spans lateral banners	\$ 1,390		
k5	Lateral banners - 6' 6" x 15' 9" (Set of 2)	\$ 1,045		
k6	Rear banner - 23' 4" x 12' 11" - installs full size, with or without backdrop <i>*available in vinyl - prices vary</i>	\$ 2,725		
L	MISCELLANEOUS	Price (USD)	Quantity	
l1	Misc_1	TBD		
l2	Misc_2	TBD		

Total for Options & Accessories \$ 33,935

SERVICES

	SERVICES	Price (USD)	Quantity	
m1	Trailer shrink wrap	\$ 700		
m2	Transport - to City of Valdez	\$ 12,750	1	\$ 12,750
m2a	Transport to Champlain, NY - includes customs paperwork	\$ 1,200		
m3	Training course - 3 day comprehensive (subject to options chosen) - maximum 4 technicians	\$ 2,440	1	\$ 2,440
m4	Trainer expenses - to, in & from training site (n/a when training given at Stageline)	\$ 6,200	1	\$ 6,200

Total for Services \$ 21,390

TRANSPORTATION, TRAINING AND TRAINER'S EXPENSES WILL BE INVOICED SEPARATELY.

*Prices & specifications subject to change without notice

Stageline SL100 - Sales Quote 2018



Costs related to transportation, training and trainer expenses (travel, accommodation and per diem) not included.
EXW: L'Assomption, Quebec, Canada

Stageline Mobile Stage Inc.
700 Marsolais Street, L'Assomption, Quebec, Canada J5W 2G9

Tel.: (450) 589-1063, Fax: (450) 589-1711
www.stageline.com